



# NEWS

**GUADALUPE-BLANCO RIVER AUTHORITY  
933 EAST COURT STREET, SEGUIN, TEXAS 78155  
TEL: [830] 379-5822 FAX [830] 379-9718**

## **Phase I of Lake Placid Repairs to Begin March 29**

**FOR IMMEDIATE RELEASE**, March 24, 2005

Contact: Judy Gardner or Tammy Beutnagel, [830] 379-5822, email [jgardner@gbra.org](mailto:jgardner@gbra.org) or [tbeutnagel@gbra.org](mailto:tbeutnagel@gbra.org)

**SEGUIN-** The Guadalupe-Blanco River Authority (GBRA) will begin initial repairs known as Phase I to the TP-4 (Lake Placid) spill gates on Tuesday, March 29. This phase of the repairs is estimated to take 3-4 weeks.

The second phase of repairs will be performed with the hydroelectric gates in the “up position”. It is estimated that this phase will take an additional 6-8 weeks. The lake will be near the normal elevation during the second phase of the repairs.

To assist in the repairs, release at Canyon Lake will decrease to 1,100 cubic feet per second (cfs) on Friday, March 25, and be further reduced again on Monday morning, March 28 to 600 cfs. This flow rate will remain into effect for 3-4 weeks if weather permits.

Until the initial repairs at the hydroelectric spillgates are completed, and the gates are in the “up position”, an alternate hydro release plan will be in effect. The plan involves lowering Lake Dunlap 1.6 feet during the nighttime hours by passing approximately 1,800 cfs through the Hydro System. During the day, Dunlap will be refilled while passing 450 cfs through the power plant. Lake Dunlap will be approximately 20 inches below the normal elevation Monday through Friday beginning at 5:00 AM each morning and returning to normal elevation by 5:00 PM each afternoon. The 1,800 cfs flow will begin at 6:00 PM each afternoon and continue until 5:00 AM each morning, Sunday through Thursday of each week.